

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 175-21,414-0000
SW SW NW, SEC. 8, T 32 S, R 33 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corp.
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

2310 feet from ~~NYX~~ section line

330 feet from W/E section line

Lease Name Morgan "I" Well # 2

County Seward 190.78

Well Total Depth 5870 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1542

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 15 Month: 12 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-651-3005

logs: 5 1/2" at 5838', PBTD 4300', Perfs at 5684-5700, 5478-5548, 4586-94, 4169-78'

1st plug pump 200 lbs. hulls and 25 sx cement, displace to 4000',

2nd plug spot 25 sx cement at 4169', 3rd plug spot 25 sx cement at 2700',

4th plug spot 50 sx cement at 1575', 5th plug spot 40 sx cement at 700',

6th plug spot 10 sx cement at 40 to 3'.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC. 21 1995
12-21-95
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received DEC. 21 1995 Gary Winters

Plugging Operations attended by Agent?: All X None _____ (TECHNICIAN)

Operations Completed: Hour: 5 p.m. Day: 15 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pump 200 lbs. hulls and 25 sx cement, displaced to 4000',

2nd plug spotted 25 sx cement at 4169', 3rd plug spotted 25 sx cement at 2700',

4th plug spotted 50 sx cement at 1575', 5th plug spotted 40 sx cement at 700',

6th plug with 10 sx cement at 40-3'.

Remarks: Used common cement by Sargent & Horton. Recovered 2700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

1-8-96
44424

Signed Gary Winters (TECHNICIAN)