

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 175-21,518-0000
App. W/2 SW SE SE, SEC. 13, T 32 S, R 33 W/2 XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 7457
Operator: Elder & Vaughn Inc.
Name:
Address P.O. Box 18938
Oklahoma City, OK 73154

330 feet from S section line
1155 feet from E section line
Lease Name Kane Trust Well # 1-13
County Seward 168.51
Well Total Depth 5185 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1675

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____ never produced

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 6 Month: 5 Year: 19 96
Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Work: 5 1/2" at 3241' w/210 sx cement, PBTD 3212', Perfs at 2806-31'
1st plug pump 300 lbs. hulls and 25 sx cement to bottom,
2nd plug at 1700' with 50 sx cement,
3rd plug at 700' with 25 sx cement,
4th plug at 40' with 10 sx cement. Mud spacer between plugs.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4 p.m. Day: 6 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug spotted plug at 2631' to 2431' with 200 lbs. hulls and 25 sx cement.

2nd plug spotted a 50 sx plug at 1700',
3rd plug spotted a 25 sx cement plug at 700',
4th plug spotted a 10 sx cement plug at 40-0'.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 14 1996

Remarks: Used common cement by Sargent & Horton. Recovered 2207' of 5 1/2" casing. AS
(If additional description is necessary, use BACK of this form.)

(I (did / ~~XXXXXX~~) observe this plugging.
DATE 5-23-96
W.M. # 45628

Signed *Gary Winters* (TECHNICIAN)