

SEP 4 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,11B-0000
100' W of C NW SW, SEC. 14, T 32 S, R 33 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8563

Operator: Oakwood Resources Inc.
Name & Address P.O. Box 740516
Dallas, TX 75374-0516

1980 feet from S section line
4720 feet from E section line

Lease Name Lemert-Printz Well # 1-14

County Seward 195.20

Well Total Depth 6006 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1615

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 2 p.m. Day: 2 Month: 9 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5026' PBDT 4948' Perfs at 4793-4803, 4812-17, 4934-40'

1st plug pump 1 sx hulls and 20 sx cement,

2nd plug on stub with 40 sx cement,

3rd plug at 1645' with 40 sx cement,

4th plug at 800' with 30 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 4 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pump 1 1/2 sx hulls and 20 sx cement and heavy mud,

2nd plug pump 40 sx cement at 2500',

3rd plug pump 40 sx cement at 1645',

4th plug pump 30 sx cement at 750',

5th plug pump 10 sx cement at 0-40'. Heavy mud between all plugs.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1987
9-10-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2523' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Glen R. Barlow
(TECHNICIAN)

SEP 11 1987

22