

1 090130

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,834 -0000 81 R
C SE SE, SEC. 16, T 32 S, R 33 W X E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3871

Operator: Hugoton Energy
Name & Address: 229 E. William, Suite 500
Wichita, KS 67202

500 feet from S section line

500 feet from E section line

Lease Name Franz Well # 1
County Seward 195.16

Well Total Depth 6005 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1650

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10:10 a.m. Day: 10 Month: 10 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 6003' w/200 sx cement, PBSD 5950', Perfs at 5698-5753'

1st plug pump 2 1/2 sx hulls and 25 sx cement on bottom,

2nd plug pump 50 sx cement on stub,

3rd plug pump 50 sx cement at 1640',

4th plug pump 40 sx cement at 600', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 10 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 1/2 sx hulls and 25 sx cement over perfs,

2nd plug spotted 50 sx cement at 2700',

3rd plug pulled to 1640' and spotted 50 sx cement,

4th plug pulled to 600' and spotted 40 sx cement,

5th plug pumped 10 sx cement at 40'. Cement circulated.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1991

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

DATE 10-30-91
33552

Signed [Signature] (TECHNICIAN)