

To: 1 120399
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,246 - 0000113 *R*
N/2 N/2 NW, SEC. 16, T. 32 S, R 33 W/E
4950 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO INC.
Name: BEREXCO INC.
Address 970 Fourth Financial Ctr.
Wichita, KS 67202

Lease Name Coral Well # I-16
County Seward
Well Total Depth 6050 196.62 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1658

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor BEREDCO INC. License Number 5147
Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 8 Month: 4 Year: 19 92

Plugging proposal received from Stan Wycoff
(company name) BEREDCO INC. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1638-74'
1st plug at Base of Council Grove with 100 sx cement,
2nd plug at 1680' with 50 sx cement, 3rd plug at 840' with 40 sx cement,
4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10 a.m. Day: 8 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2850' with 100 sx cement,
2nd plug at 1680' with 50 sx cement,
3rd plug at 840' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

I (XXXX/ did not) observe this plugging.
4-27-92
35061

Signed Duane Rankin
(TECHNICIAN) *DR*