

1100342

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-21,302-0001  
C NE SE SEC. 18, T 32 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LONGCOR B WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 188.50

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 5800 FEET

OPERATOR: OXY USA INC

PRODUCTION CSG: SIZE 5 1/2" @ 2790' WITH 460 SX

NAME AND BOX 2528

SURFACE CASING: SIZE 8 1/2" @ 1530' WITH 725 SX

ADDRESS LIBERAL, KS 67950-2528

STATE CORPORATION COMMISSION

ABANDONED OIL WELL        GAS WELL X INPUT WELL        SWD APR 10 2000 D/A       

OTHER WELL AS HEREINAFTER INDICATED        CONSERVATION DIVISION

Wichita, Kansas

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 29 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC. (PHONE) 580-854-6515

WERE: PERFS AT 2431-33, 2459-63, 2488-92, 2510-12, 2538-42

1ST PLUG MIX 400# HULLS AND 25 SX CEMENT TO PLUG PERFS OFF FROM 2431-2231. PERFS SQUEEZED

AT 800 PSI. CIRCULATE HOLE. 2ND PLUG PRESSURE UP BACKSIDE WITH 10 SX CEMENT TO 500 PSI.

3RD PLUG SPOT 25 SX CEMENT PLUG AT 1630' TO 1430'. LOAD HOLE WITH MUD. 4TH PLUG SPOT

65 SX CEMENT PLUG FROM 550' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART        NONE       

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 29 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT       

1ST PLUG MIX 400# HULLS AND 25 SX CEMENT TO PLUG PERFS OFF FROM 2431-2231. PERFS SQUEEZED

AT 800 PSI. CIRCULATE HOLE. 2ND PLUG PRESSURE UP BACKSIDE WITH 10 SX CEMENT TO 500 PSI.

3RD PLUG SPOT 25 SX CEMENT PLUG AT 1630' TO 1430'. LOAD HOLE WITH MUD. 4TH PLUG SPOT

65 SX CEMENT FROM 550' TO 0'.

REMARKS: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Gary Winters  
(TECHNICIAN)

4/12/00  
061533

FORM CP-2/3