

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,290 - 0000

C SW SW, SEC. 19, T 32 S, R 33
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6120

Lease Name Hitch Well # 1-19

Operator: Cabot Oil & Gas Corporation

County Seward

Name:
Address 9400 N. Broadway, Ste. 608

Well Total Depth 6275 203.93 feet

Oklahoma City, OK 73114

Conductor Pipe: Size 20" feet 40'

Surface Casing: Size 8 5/8" feet 1526

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt.1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 13 Month: 4 Year: 19 94

Plugging proposal received from Don Horton

{company name} Sargent & Horton Plugging Inc. (phone) 405-854-6515

logs: 4 1/2" at 2746' w/575 sx cement, PBTD 2696', Perfs at 2491-94, 2521-35, 2571-85'

1st plug set CIBP at 2400' with 2 sx cement on top,

2nd plug at 1550' with 20 sx cement,

3rd plug at 700' with 20 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 13 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2400' with 2 sx cement on top,

2nd plug at 1550' with 20 sx cement,

3rd plug at 700' with 20 sx cement,

4th plug at 40-0' with 5 sx cement.

RECEIVED
STAFF CORPORATION COMMISSION

APR 20 1994

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent & Horton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

4-25-94
40325
4-13
(If additional description is necessary, use BACK of this form.)
I (d.l.d. / 40325) observe this plugging.

Signed

Lynn R. Bostan
(TECHNICIAN)