

15-175-00266-0000
720 R

To: 1 020300
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available
SEC. 21, T 32 S, R 33 W/E
1650 feet from section line
1320 feet from section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6120

Lease Name Mercer Well # 2
County Seward 85.57
Well Total Depth 2633 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 390

Operator: Cabot Petroleum Corporation
Name & Address P.O. Box 9999
Amarillo, TX 79105

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9 a.m. Day: 28 Month: 2 Year: 19 90

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 816-624-7455

were: 7" at 2483' 5 1/2" slotted liner at 2442-2577', 5 1/2" liner at 2443-2571' PBTB 2577'

1st plug run tubing to 2430' with 50 sx cement, 2nd plug at 1800' with 50 sx cement,
3rd plug at 800' with 50 sx cement, 4th plug at 410' with 50 sx cement,
5th plug at 40' with 15 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:15 p.m. Day: 1 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 50 sx cement at perf. liner, tag
with 2 7/8" at 1945',
2nd plug loaded hole with heavy mud, pumped 50 sx cement at 1800',
3rd plug ran tubing to 800', loaded hole with mud, pumped 50 sx cement at 800',
4th plug pulled tubing to 410', pumped 50 sx cement,
5th plug pulled tubing to 40', pumped 15 sx cement.

Remarks: Used common cement by Sargent's. Recovered 800' of 7" casing.
(if additional description is necessary, use BACK of this form.)

DATE MAR 26 1990
WICHITA CONSERVATION DIVISION

Signed Glenn R. Barlow (TECHNICIAN)