

1100213

TO: 3-27

API NUMBER 15-175 -20,236-0000

STATE CORPORATION COMMISSION NE NE, SEC. 22, T 32 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2135 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME LEMERT WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY SEWARD 191.75

OPERATOR LICENSE # 3062 WELL TOTAL DEPTH 5900 FEET

OPERATOR: QUESTA ENERGY CORP. PRODUCTION CSG: SIZE 4 1/2" FEET 5875' W/325 SX

NAME AND P.O. BOX 19297 SURFACE CSG 8 5/8" FEET 1584' W/650 SX

ADDRESS AMARILLO TEXAS 79114

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CASING PULLING LICENSE NUMBER 6547

ADDRESS P.O. BOX 506 LIBERAL KANSAS 67905-0506

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 27 MONTH: 3 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ROB MCGARRAUGH

(COMPANY NAME) QUESTA ENERGY CORP. (PHONE) 806-435-4622

WERE: 1ST: MIX 20 SX PLUG FROM 4994'-4756'. 2ND: MIX 50 SX PLUG FROM 1593'-1436'.

3RD: MIX 50 SX PLUG FROM 800'- 680'. 4TH: MIX 10 SX PLUG FROM 40'-0.

PLUGGING PROPSAL RECEIVED BY: STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 27 MONTH: 3 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST: MIXED 100# HULLS AND 20SX CEMENT AND DISPLACED TO 4884' AT

300 PSI. 2ND SPOT 50 SX CEMENT PLUG AT 1615'

3RD SPOT 50 SX CEMENT PLUG AT 680'

4TH SPOT 10 SX CEMENT AT 40' TO 0'

REMARKS: USED 130 SXS. OF ELTORO PORTLAND CEMENT. RECOVERED 2530' OF 4 1/2" CAS.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary L. Minter
(TECHNICIAN) FORM CP-2/3^{PI}

50358

3-27

APR 4-8-98