

To: 1 060977
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,447-0000
SE SE, SEC. 22, 'T' 32 S, R 33 W/R
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Betty Lemert B Well # 2

Operator: Amoco Production Company

County Seward 195.00

Name & Address P.O. Box 432

Well Total Depth 6000 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1613

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11:30 a.m. Day: 8 Month: 7 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 6000' PBTD 5508' Perfs at 5438-48'

1st plug set CIBP at 5300' and dump 2 sx cement on top,
2nd plug pump 50 sx cement on stub, 3rd plug pump 50 sx cement at base of surface casing,
4th plug pump 35 sx cement at 800', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 8 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5313' and dumped 2 sx cement on top,

2nd plug pumped 50 sx cement on stub at 1640',

3rd plug pumped 35 sx cement at 800',

4th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1640' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging. 10 1987
7-10-87

DATE 7-10-87

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)

WELL NO. 17462