

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-20, 284-0000
NENE, SEC. 22, T. 32 S., R. 33 E

RECEIVED
KANSAS CORP COMM

TECHNICIAN'S PLUGGING REPORT 1998 APR -9 @ 12:20
733 feet from N section line
660 feet from E section line

Operator License 103062 Lease Name Lemert Well # 3
Operator: Questa Energy Corp. County Seward 164.13
Name: Address P.O. Box 19297 Well Total Depth 5050 feet
Amarillo, TX 79114 Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1582

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing pulling Service License Number 6547
Address P.O. Box 506 Liberal, Ks, 67905

Company to plug at: Hour: 9:00 AM Day: 31 Month: 3 Year: 19 98

Plugging proposal received from Steve Durrant
(company name) Kirby Lillard w/sargents (phone) 316-624-7455

were: 4 1/2" @ 5050' PBTD @ 4998' Perfor: 4899-4906

1st plug mix + pump 100 # cottonseed hulls + 20sx cement + displace to top of Perf. 2nd spot thru tubing 50sx cement @ 1607'

3rd spot thru tubing 680' w/ 4 1/2" perf hole from 40' to 0' w/ 10sx -

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 Day: 31 Month: 03 Year: 19 98

ACTUAL PLUGGING REPORT 1st pumped 100 # hulls + 20sx cement to 4899'. 2nd loaded hole w/ gel and displaced 50sx plug @ 1607', 2nd pulled tubing to 680' and displaced 50sx cement, 3rd pulled tubing to 40' and displace hole w/ 10sx cement -

Remarks: Common Cement by Sargents Rec' 2435' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.
Gary Winters 50346 Signed Steve Durrant
(TECHNICIAN)