

9-15-87

API NUMBER 15-175-20,433-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW NW SE, SEC. 26, T 32 S, R 33 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7720

Lease Name Carlile Well # 3-26
County Seward 196.63

Operator: Burnett Corporation
Name & Address First Nat'l Bank Bldg., Suite 450
Amarillo, TX 79101

Well Total Depth 6050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1557

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 8 a.m. Day: 25 Month: 9 Year: 1987

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5756' PBTD 5756' Perfs at 5654-5660'

1st plug pump 1 sx hulls and 25 sx cement at 5400'

2nd plug pump 40 sx cement at free point,

3rd plug pump 40 sx cement at 1580'

4th plug pump 25 sx cement at 600', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1 p.m. Day: 28 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement to 5400', spot thru casing

2nd plug at 2600' with 40 sx cement,

3rd plug at 1580' with 40 sx cement,

4th plug at 600' with 25 sx cement,

5th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3128' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

Signed Glenn P. Barlow
(TECHNICIAN)

10-19-87
18557