

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,471-0000
C NE NW, SEC. 26, T 32 S, R 33 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7720
Operator: Burnett Corporation
Name & Address First Nat'l Bank Bldg., Suite 450
Amarillo, TX 79101

Lease Name Carlile Well 12-26
County Seward 190.26
Well Total Depth 5854 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1575

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 8 a.m. Day: 29 Month: 9 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5823' Perfs at 5635-47' Elevation 2745'GL

1st plug pump 1 sx hulls and 20 sx cement at 5800', 2nd plug pump 40 sx cement at 2500',
3rd plug pump 40 sx cement at 1600', 4th plug pump 35 sx cement at 650',
5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1 p.m. Day: 30 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at 5800',
2nd plug pumped 40 sx cement at 2500',
3rd plug pumped 40 sx cement at 1600',
4th plug pump 35 sx cement at 650',
5th plug pumped 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1987

CONSERVATION DIVISION
Wichita Kansas

Remarks: Used common cement by Sargent's. Recovered 3138' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXX~~) observe this plugging.

10-6-87
18377

Signed Glenn R Barlow
(TECHNICIAN)