

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,479-0000

NW SEC. 26, T. 32S, R. 33W

C. NE NW NW FEET FROM N/S SECTION LINE

TECHNICIAN'S PLUGGING REPORT

_____ FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 5447

LEASE NAME COOPER "G" WELL # 2

OPERATOR: Cities Service Co
NAME & ADDRESS 3545 N.W. 58TH ST
OKLAHOMA CITY, OK
73112

COUNTY SEWARD

WELL TOTAL DEPTH 5800 ^{4188.5'} FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8 FEET 1572

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR DACO, INC. LICENSE NUMBER 6416

ADDRESS DRAWER 3010, BORGER, TX 79007

COMPANY TO PLUG AT: HOUR: 2 pm DAY: 9 MONTH: AUG. YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Charles Glasscock

(COMPANY NAME) Cities Service (PHONE) _____

WERE: use Class H cement - set Cast Iron Bridge Plug @
4815 tagged w/ 1/2 sy - pull 5 1/2" casing - Free point
at 2520' with a plug of 35 sy - set a 50 sy plug
@ 1620' - set a plug of 50 sy @ 810' - capped with
a 15 sy plug @ 40'

PLUGGING PROPOSAL RECEIVED BY R. Bartluttan
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR: 10 am DAY: 12 MONTH: Aug. YEAR: 1983

ACTUAL PLUGGING REPORT plugged as proposed.
Cemented by Daco.

REMARKS: 5 1/2" set @ 5156 - PBD @ 4908 - Perfs @
4876 - 4888 - CIBP @ 4815 w/ 1/2 sy

I (~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED R. Bartluttan ✓
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

8-19-83 **AUG 19 1983**

FORM CP-2/3
REV. 6-83

5268-W
CONSERVATION DIVISION
Wichita, Kansas