

To: 1. 5-10
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 175-20,575-0000

W/2 NW NE, SEC. 26, T. 32 S, R. 33 WXX

4605 feet from S section line

2300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Cooper G Well # 3

Operator: OXY USA Inc.

County Seward 189.74

Name & Address P.O. Box 300

Well Total Depth 5838 feet

Tulsa, OK 74102

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1584'

Abandoned Oil Well Gas Well Input Well SMD Well O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services & J.W. Gibson License Number

Address

Company to plug at: Hour: 9 a.m. Day: 9 Month: 5 Year: 19 97

Plugging proposal received from Reid Wilson 5-16-97

(company name) Halliburton Services (phone) 316-629-3578

logs: 5 1/2" at 5837' w/150 sx cement, PBSD 5694', Perfs at 5642-48'

1st plug set CIBP at 5730' with 2 sx cement,

Plug through tubing:

2nd plug spot 200 sx cement from 3205-2200', 3rd plug spot 50 sx cement at 1634',

4th plug spot 40 sx cement at 648', 5th plug spot 10 sx cement at 40-0'.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:41 a.m. Day: 10 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5730' with 2 sx cement on top,

Ran freepoint, shot casing at 3395', pulled out casing and plugged through tubing:

2nd plug spotted 200 sx cement from 3205-2200', displaced with gel,

3rd plug spotted 50 sx cement at 1634', displaced with gel,

4th plug spotted 40 sx cement at 648',

5th plug spotted 10 sx cement from 40-0'.

Remarks: Used Halliburton Lite 6% gel 2% cc by Halliburton. Recovered 3395' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Gary Winters (TECHNICIAN)

48130

5-10