

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 129-20,765 - 0000
100' E of
C S/2, SEC. 35, T 34 S, R 42 W/4
1320 feet from S section line
2540 feet from E section line
Unit

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Taloga Morrow Well # 503
County Morton 152.75
Well Total Depth 4700 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1390

Abandoned Oil Well Gas Well Input Well SWO Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 13 Month: 2 Year: 19 96

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

logs: 4 1/2" at 4695' w/275 sx cement, PBTD 4550', Perfs at 4526-38, 4562-88'

1st plug pump 2 sx hulls and 20 sx cement to bottom,

2nd plug at 1420' with 50 sx cement,

3rd plug at 650' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 13 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement at 4526-4326',

2nd plug at 1420' with 50 sx cement,

3rd plug at 650-550' with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

2-20-96

RECEIVED
KANSAS CORP COMM
1996 FEB 20 11 28 AM

Remarks: Used common cement by Sargent & Horton. Recovered 2580' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

44889

2-13

Signed Gay Matus
(TECHNICIAN)