

1 020282

37 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,766-0000
100' S of
C W/2, SEC. 35, T 34 S, R 42 W/E
2540 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Watson "B" Well # 1
County Morton 159.45
Well Total Depth 4906 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1366

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers Service License Number 6547
Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 30 Month: 12 Year: 19 89

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pullers Service (phone) 316-624-7455

were: 5 1/2" at 4700' Perfs at 4490-4580'-all squeezed off Estimated TOC 3836'

1st plug set CIBP at 4600' on wireline with 2 sx cement on top with bailer,

2nd plug circulate hole with mud, spot 30 sx cement at cut off, 3rd plug pump 50 sx cement

at 1416-1216', 4th plug pump 35 sx cement at 700',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 p.m. Day: 1 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4600' on wireline with 2 sx cement on top
with bailer,

2nd plug circulated hole with mud, spotted 30 sx cement at 2800',

3rd plug pumped 50 sx cement at 1416-1216',

4th plug pumped 35 sx cement at 700',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2830' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1990

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 12/20/89
WV. NO. 27173

Signed Glenn R. Barlow
(TECHNICIAN)