

1 022401
To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

15-129-10547-000117P
Docket #E-15,849
API NUMBER 15- Drill Completion Date 4/30/56

C NW SEC. 35 T. 34 S. R. 42 W/2
3960 feet from S section line
3960 feet from E section line

Lease Name Taloga Mor "G" Well # 302
County Morton 150.18
Well Total Depth 4621 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1530

Abandoned Oil Well Gas Well Input Well x SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 4 p.m. Day: 10 Month: 9 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4621', Perfs at 4514-22, 4532-44, 4548-56'
w/1000 sx cem.

1st plug pump 1 sx hulls and 20 sx cement at perfs with tubing, load hole with mud,

2nd plug pump 30 sx cement at 2030', 3rd plug pump 40 sx cement at 1570-1470',

4th plug pump 30 sx cement at 650-550', 5th plug pump 10 sx cement at 40' to -4'.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:15 p.m. Day: 12 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs with tubing
at 4500', loaded hole with mud,

2nd plug pumped 30 sx cement at 2030',

3rd plug pumped 40 sx cement at 1570-1470'

4th plug pumped 30 sx cement at 650-550',

5th plug pumped 10 sx cement at 40' to -4'.

Remarks: Used common cement by Sargent's. Recovered 2030' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(XXXX) did not observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)