

1100241

TO: STATE CORPORATION COMMISSION

9-18

API NUMBER 15-119-20,121-0001
NW SE SEC. 6, T 33 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ANGELL UNIT WELL # 5

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE 190.62

OPERATOR LICENSE # 04570

WELL TOTAL DEPTH 5865 FEET

OPERATOR: SAMEDAN OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2 " FEET 5865

NAME AND ADDRESS 9400 N BROADWAY, SUITE 700 SURFACE CASING: SIZE 8 5/8 " FEET 1533 ' OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CSG. PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 17 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM LEE FARMER

(COMPANY NAME) SAMEDEAN OIL (PHONE) 405-262-7778

WERE: PERFS AT 5728-6756

1ST PLUG SET 25 SX CEMENT WITH 100# HULLS. DISPLACE HOLE WITH MUD.

2ND PLUG AT 1583' WITH 50 SX CEMENT,

3RD PLUG AT SX AT 500' WITH 30 SX CEMENT,

4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 18 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET 25 SX CEMENT WITH 200# HULLS AT 5678' DISPLACE WITH MUD.

2ND PLUG AT 1583' WITH 50 SX CEMENT.

3RD PLUG AT 500' WITH 40 SX CEMENT.

4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

RECEIVED KANSAS CORPORATION COMMISSION

SEP 24 1998

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2715' OF 5 1/2" CASING (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACKS OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

51394