

1100244

TO: STATE CORPORATION COMMISSION

9-29

API NUMBER 15-119-20,114-0001
NE SW SEC. 6, T 33 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ANGELL UNIT WELL # 4

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 190.58

OPERATOR LICENSE # 04570 WELL TOTAL DEPTH 5864 FEET

OPERATOR: SAMEDAN OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2 " FEET 5862

NAME AND ADDRESS 9400 N BROADWAY, SUITE 700 SURFACE CASING: SIZE 8 5/8 " FEET 1557'

ADDRESS OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL E-27,163 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CSG. PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 29 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SAMEDEAN OIL (PHONE) 405-262-7778

WERE: PERFS AT 5725-5760

SET 25 SX CEMENT WITH 100# COTTON SEED HULLS AT 5675'. DISPLACE HOLE WITH 9.2 PPG PLUG

MUD. SET 50 SX CEMENT AT 1587'. SET 30 SX CEMENT AT 500'. SET 10 SX CEMENT AT 40'-3'.

CUT OFF SURFACE CASING 4' BELOW G.L.. INSTALL ID PLATE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 29 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG ON 9-28-98 SET 25 SX CEMENT & 200# HULLS. THE PLUG FELL. ON 9-29-98 REPLUGGED WITH

25 SX CEMENT & 200# HULLS. 2ND PLUG AT 1587' WITH 50 SX CEMENT. 10-10-98

3RD PLUG AT 500' WITH 40 SX CEMENT.

4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2730' OF 5 1/2" CASING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Gary Winters

(TECHNICIAN)

FORM CP-2/3

[Signature]

DATE 09 29 1998

51423