

1100243

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,165-0001  
NE NE SEC. 6, T 33 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ANGELL UNIT WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE 187.85

OPERATOR LICENSE # 04570

WELL TOTAL DEPTH 5780 FEET

OPERATOR: SAMEDAN OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2 " FEET 5780

NAME AND 9400 N BROADWAY, SUITE 700 SURFACE CASING: SIZE 8 5/8 " FEET 1521'

ADDRESS OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL X GAS WELL        INPUT WELL        SWD WELL        D/A       

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR SARGENTS CSG. PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 8:30 AM DAY: 24 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KIRBY

(COMPANY NAME) SAMEDEAN OIL (PHONE) 405-262-7778

WERE: PERFS AT 5708-5720

SET 25 SX CEMENT WITH 100# COTTON SEED HULLS AT 5658'. DISPLACE HOLE WITH 9.2 PPG PLUG

MUD. SET 50 SX CEMENT AT 1550'. SET 30 SX CEMENT AT 500'. SET 10 SX CEMENT AT 40'-3'.

CUT OFF SURFACE CASING 4' BELOW G.L.. INSTALL ID PLATE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART        NONE       

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 24 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT 10-1-98

1ST PLUG AT 1550' WITH 50 SX CEMENT.

2ND PLUG AT 500' WITH 40 SX CEMENT.

3RD PLUG AT 40'-0' WITH 10 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS RECOVERED 1500' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID)        OBSERVE THIS PLUGGING.

SIGNED Gary Winters  
(TECHNICIAN) FORM CP-2/3

10-2-98  
51411

1998 OCT -1 10 12 22  
KANSAS CORPORATION COMMISSION