

1100242

TO: STATE CORPORATION COMMISSION

9-22 API NUMBER 15-119-20,123 - 0001
C SE NW SEC. 6, T 33 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 677 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2176 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ANGELL WSW WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 191.75

OPERATOR LICENSE # 04570 WELL TOTAL DEPTH 5900 FEET

OPERATOR: SAMEDAN OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2 " FEET 4057

NAME AND ADDRESS 9400 N BROADWAY, SUITE 700 SURFACE CASING: SIZE 8 5/8 " FEET 1522'

ADDRESS OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED WATER SUPPLY WELL

PLUGGING CONTRACTOR SARGENTS CSG. PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 8:30 AM DAY: 22 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KIRBY

(COMPANY NAME) SAMEDEAN OIL (PHONE) 405-262-7778

WERE: PERFS AT 3515-3620

1ST PLUG SET 25 SX CEMENT WITH 100# HULLS FROM 3620 TO 3400'.

2ND PLUG SET 50 SX CEMENT AT 1564'.

3RD PLUG SET 30 SX CEMENT AT 500'.

4TH PLUG SET 10 SX CEMENT AT 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 22 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET 25 SX CEMENT WITH 200# HULLS FROM 3620-3400'.

2ND PLUG SET 50 SX CEMENT AT 1564'.

3RD PLUG SET 40 SX CEMENT AT 500'.

4TH PLUG SET 10 SX CEMENT AT 40' TO 0'.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 24 1998

CONSERVATION DIVISION
WICHITA, KS

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2520' OF 5 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters
(TECHNICIAN)

FORM CP-2/3

51395