

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,541-0800

C NW SE, SEC. 7, T 33 S, R 29 W/EX

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Lease Name Cartzdafner Well # 1-7

Operator: Imperial Oil Company

County Meade 193.05

Name & Address 720 4th Financial Center

Well Total Depth 5940 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1588

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 19 Month: December Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5939' Perfs at 5770-78'

1st plug pump 50 sx cement to 5300'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:00 pm Day: 19 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5939' Perfs at 5770-78'

1st plug pumped 50 sx cement to 5300', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in pressure 600 psi

JAN 02 1985

Remarks: Recovered 4000' 4 1/2" casing. Used common 60/40 Pozmix 2% gel 3% cc by Halliburton (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Paul A. Luthin (TECHNICIAN)

1-16-85
6524