

15-175-10085-0000

To: 1 110048
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

C. SW SW, SEC. 24, T. 33 S, R 31 W/E
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Wheatly "B" Well # 1

Operator: A.L. Abercrombie, Inc.
Name & Address
801 Union Center
Wichita, KS 67202

County Seward 193.80

Well Total Depth 5963 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1242

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS

Company to plug at: Hour: 11:45 a.m. Day: 15 Month: 1 Year: 19 87

Plugging proposal received from Ronny Hoover

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 5776' Open holes

1st plug sand back to 5720' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 35 sx gel, 60 sx cement, 10 sx gel, 160 sx cement.

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 15 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 5720' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 30 sx gel, 60 sx cement, 15 sx gel, and 160 sx cement.

Cement dropped approx. 300 ft, topped off with 3 yds of redi mix. STATE CORPORATION COMMISSION

JAN 21 1987-21-87

Recovered 2420' of 4 1/2" casing.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INFORMED observe this plugging.

Signed James P. Kay (TECHNICIAN)