

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- DRILL COMPLETION DATE 10/16/61

App. C NE SW, SEC. 26, T 33 S, R 31 W/4  
3310 feet from NX section line  
3200 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Frederick Well # 5

Operator: A.L. Abercrombie, Inc.

County Seward

Name & Address Rt. 1, Box 56

Well Total Depth 5920 192.40 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1228

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 14 Month: 12 Year: 19 93

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 5 1/2" at 5916' w/160 sx cement, PBD 5903', Perfs at 5838-88, Packer at 5830',  
Perfs at 4313-18', DV tool at 4460' w/160 sx

1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,

Spot plugs through casing: 2nd plug at 2500' with 40 sx cement, 3rd plug at 1270' w/50 sx cem.,

4th plug at 600' with 40 sx cement, 5th plug at 100' with 25 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 14 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through 5 1/2" casing:

2nd plug at 2500' with 40 sx cement, 3rd plug at 1270' with 50 sx cement,

4th plug at 600' with 40 sx cement,

5th plug at 200' with 30 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing. DEC 16 1993  
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)

39565