

1 110190

7-2

15-175-10064-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 1960

C SW NE, SEC. 26, T 33 S, R 31 W/E

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Frederick Well # 1

Operator: A.L. Abercrombie, Inc.

County Seward 232.37

Name & Address Rt. 1, Box 56

Well Total Depth (7150) feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 658

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour 2:30 p.m. Day: 2 Month: 7 Year: 1993

Plugging proposal received from Dallas

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 5995' w/300 sx cement, PBD 5895', Perfs at 5848-54, 5860-88'

Pump 3 sx hulls, 50 sx cement, gel to 1250', cement to 0'

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:45 p.m. Day: 2 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT Pumped 3 sx hulls and 50 sx cement at 5848' leaving 100' to 5748', displaced with gel spacer to 1240', cemented to surface with 125 sx cement.

NOTE: 5 1/2" perforated and squeezed from 1240' to surface.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(if additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

JUL - 9 1993

INVOICED JUL 19 1993

(do not check) observe this plugging.

Signed James R. Kay (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

DATE 38137