

1 110189

7-2

15-175-10067-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- Drilled 1961

C NW NE, SEC. 26, T 33 S, R 31 WXE
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name & Address Rt. 1, Box 56
Great Bend, KS 67530.

Lease Name Frederick Well # 4
County Seward 191.75
Well Total Depth 5900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1246

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 1:30 p.m. Day: 2 Month: 7 Year: 19 93

Plugging proposal received from Dallas
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 5895' w/250 sx cement, Perfs at 3098-3104, 3116-21, 3130-33, 3156-61, 3199-3201, 3228-30'

1st plug sand back to 3050' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1246' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 2 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3050' and dumped 5 sx cement on top of sand through⁴ bailer,

2nd plug at 1246' with 50 sx cement,

3rd plug pulled to 700' and spotted 40 sx cement,

4th plug pulled to 40' and pumped 10 sx cement to surface.

Remarks: Recovered 1500' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE JUL 19 1993

UNV. NO. 38136

Signed James R. Kapp
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1993

CONSERVATION DIVISION
Wichita, Kansas