

1001533

15-175-00210-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API. NUMBER 15- Comp. 11/28/60
C NE NE, SEC. 26, T 7, R 33 S, R 31 W/8
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393

Lease Name Frederick Well # 3
County Seward
Well Total Depth 5931 192.75 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1242

Operator: A.L. Abercrombie, Inc.
Name
Address Rt. 1, Box 56
Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9:30 a.m. Day: 15 Month: 9 Year: 1994

Plugging proposal received from Kevin Strube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 5886' w/195 sx cement. PRTD 5851'. Perfs at 4466-70'
1st plug pump 2 sx hulls and 25 sx cement, displace to 4300',
2nd plug pump 60 sx cement at 1320', 3rd plug pump 40 sx cement at 600',
4th plug pump 50 sx cement at 140'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 15 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 4300',
2nd plug pumped 60 sx cement at 1320',
3rd plug pumped 40 sx cement at 600',
4th plug pumped 50 sx cement at 150'.

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did ~~XXXXXX~~) observe this plugging.

9-28-94
41285

Signed Richard W. Lacey
(TECHNICIAN)