

15-175-00092-000  
R

1 360416

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Completed 10-3-52

SE SE NW, SEC. 26; T 33 S, R 31 WXX  
2970 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Jury Well # 1

Operator: Abercrombie  
Name & Address: 801 Union Center,  
Wichita, KS 67202

County Seward 192.08

Well Total Depth 5910 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 124, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 30 Month: November Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 5862' Perfs from 5582-5602'

1st plug pump 50 sx cement to bottom and push plug to 5000'

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by Paul A. Suttis (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:40 am Day: 30 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 5862' Perfs from 5582-5602'

1st plug pumped 50 sx cement to bottom and pushed plug to 5000!, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

maximum pressure 600 psi and shut in 0

DEC 05 1984

Remarks: Recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 2% gel 5% WR by K. H. Liburton  
(if additional description is necessary, use BACK of this form.)

I (did not observe) observe this plugging.

Signed Paul A. Suttis (TECHNICIAN)

INVOICED  
DATE 12-11-84  
INV. NO. 5888