

1080319

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-21,024 - 0000
W/2 NE NE SEC. 11, T 33 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CALHOON WELL # A-1

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 184.47

OPERATOR LICENSE # 30535 6/7 WELL TOTAL DEPTH 5676 FEET

OPERATOR: HARTMAN OIL CO., INC. PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 54 SURFACE CASING: SIZE 8 5/8" @ 1522' WITH SX

ADDRESS WICHITA, KS 67201 CONDUCTOR CSG: SIZE " @ '

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572

ADDRESS P.O. BOX 1856 LIBERAL, KS 67905-1856

COMPANY TO PLUG AT: HOUR: 1:00 AM DAY: 07 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM STAN MITCHELL

RECEIVED
STATE CORPORATION COMMISSION

(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

JUN 30 2000

WERE: CONSERVATION DIVISION
Wichita, Kansas

1ST PLUG AT 1550' WITH 50 SX CEMENT. 2ND PLUG AT 500' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 25 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:00 AM DAY: 07 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1550' WITH 50 SX CEMENT. 2ND PLUG AT 500' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 25 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING 7/5/00 SIGNED Kevin Strube SA (TECHNICIAN) FORM CP-2/3

