

15-119-10136-0000

1 360369

[Handwritten signature]

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 1-3-63

C E/2 NW, SEC. 11, T 33 S, R 29 W/EX

3960 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5538

Lease Name Bergner Well # 1

Operator: Tom Kat, Ltd.

County Meade 186.85

Name & Address 250 North Rock Road, Suite 325

Well Total Depth 5749 feet

Box 18122

Conductor Pipe: Size _____ feet

Wichita, KS 67218

Surface Casing: Size 8 5/8 feet 1507

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 20 Month: May Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 5745' Perfs at 5663070'

1st plug sand back to 5600' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 150 sx cement.

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:25 pm Day: 20 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 5600' and dump 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1985
5-28-85

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 350 psi and shut in 50 psi

Remarks: Recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

(~~xxx~~ / did not) observe this plugging.

Signed *Paul A. Luttie*
(TECHNICIAN)

DATE 6-6-85
8403