

1 050407

API NUMBER 15- 119-20,683-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SE SE , SEC. 12 ; T 33 S, R 29 W/E  
990 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7457  
Operator: Elder & Vaughn  
Name & Address: Box 18938  
Oklahoma City, OK 73154

Lease Name Felice Well # 1  
County Meade 200.85  
Well Total Depth 6180 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1386

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor NRG Drilling Company License Number 6666  
Address Box 1157, Liberal, KS 67901

Company to plug at: Hour: 1:30 am Day: 14 Month: December Year: 19 84

Plugging proposal received from Fred Payne  
(company name) NRG (phone) 316-624-1818

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 1410' with 40 sx cement
- 2nd plug at 720' with 40 sx cement
- 3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rat hole with 10 sx cement
- 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lucas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 am Day: 14 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1410' with 40 sx cement, 2nd plug at 720' with 40 sx cement, 3rd & 4th plugs - solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JAN 02 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton CONSERVATION DIVISION  
(If additional description is necessary, use BACK of WITHALS Form.)

I (did / did not) observe this plugging.

1-14-85  
6409

Signed Richard W. Lucas (TECHNICIAN)

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: Nov. 19, 1984  
month day year

API Number 15-119-20,683

OPERATOR: License # 7457  
Name ELDER & VAUGHN  
Address BOX 18938  
City/State/Zip OKLA. CITY, OKLA. 73154  
Contact Person JACK H. VAUGHN  
Phone 405 842-8877

1 NE. SE. SE. Sec. 12. Twp. 33. S. Rge. 29.  West  
(location)  
990 Ft North from Southeast Corner of Section  
330 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6666  
Name NRG DRILLING CO.  
City/State Liberal, Ks. 67901

Nearest lease or unit boundary line 330 feet.  
County MEADE  
Lease Name FELICE Well# J  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 350 feet  
Lowest usable water formation 400  
Depth to Bottom of usable water 450 feet  
Surface pipe by Alternate:  1  2   
Surface pipe to be set 1375 feet  
Conductor pipe if any required none feet  
Ground surface elevation est. 2435 feet MSL.  
This Authorization Expires 5-3-85  
Approved By 11-2-84

If OWWO: old well info as follows:  
Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth .....  
Projected Total Depth 6400 feet  
Projected Formation at TD Miss. St. Louis  
Expected Producing Formations Morrow. & Miss.  
I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

to Oct. 31, 1984 Signature of Operator or Agent [Signature]

Title Partner, Engineer  
MHC/WOHE 11/2/84 Form C-1 4/84

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 02 1985  
CONSERVATION DIVISION  
Wichita, Kansas