

15-119-10151-0000

JAN 0 9 1987

API NUMBER 15- N/A

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C/4  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW/4 NE/4 SEC. 12, T 33, S, R 29 W/E

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Joe S. Fletcher Well # 2

Operator: Diamond Shamrock Exploration Company  
Name & Address P.O. Box 400  
Amarillo, TX 79188-0001

County Meade 185.58

Well Total Depth 5710 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 9 5/8 feet 1531

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 12:30 p.m. Day: 7 Month: 1 Year: 1987

Plugging proposal received from Troy Cody

(company name) Diamond Shamrock (phone) 316-563-7722

were: 5 1/2" at 5710' Perfs at 5604-5622'

1st plug set CIBP at 5525' and dump 2 1/2 sx cement on top,

2nd plug on stub at 2585' with 20 sx cement stub,

3rd plug at 1555' with 50 sx cement, 4th plug at 750' with 40 sx cement,

5th plug at 40-0' with 15 sx cement.

Plugging Proposal Received by Paul Lüthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12:31 p.m. Day: 8 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5525' and dump 2 1/2 sx cement on top,

2nd plug on stub at 2585' with 20 sx cement on stub,

3rd plug at 1550' with 50 sx cement,

4th plug at 750' with 40 sx cement.

5th plug at 40-0' with 15 sx cement.

STATE CORPORATION COMMISSION  
1-12-87  
JAN 12 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 2595' of 5 1/2" casing. Used common cement by Sargent's.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Paul A. Lüthi (TECHNICIAN)

DATE 1-12-87

ENV. NO. 15872

# SCHLUMBERGER WELL SURVEYING CORPORATION

HOUSTON, TEXAS



## Laterolog

WITH GAMMA RAY

COUNTY MEADE  
 FIELD or LOCATION SEC 12-33S-29W  
 WELL JOE S. FLETCHER 2  
 COMPANY THE SHAMROCK OIL & GAS CORPORATION

COMPANY THE SHAMROCK OIL AND GAS CORPORATION  
 WELL JOE S. FLETCHER 2  
 FIELD NORTH BORGHERS UPPER MORROW  
 LOCATION SEC 12-33S-29W

COUNTY MEADE  
 STATE KANSAS

Other Survey NLL

Location of 660' FNL  
1980' FEL

*DP*

Elevation: K.B.:  
 D.F.:  
 or G.L.:

Log Depths Measured From KD 10 Ft. above GL

RUN No.	ONE				
Date	8-11-59				
First Reading	5709				
Last Reading	1530				
Feet Measured	4179				
Csg. Schlum.	1530				
Csg. Driller	1530				
Depth Reached	5712				
Bottom Driller	5715				
Mud Nat.	STARCHE				
Dens.	9.7	55			
Visc.					
Mud Resist.	.316	@ 85	F	@	F @
Res. BHT	.234	@ 115	F	@	F @
pH	6.8	@	F	@	F @
Wtr. Loss	7.4	CC 30 min		CC 30 min	CC
Rmf	.176	@ 115	F	@	F @
Rmc	--	@	F	@	F @
Size	3 3/4"				
Laterolog 3	a= 6"	l= 3'		a=	l=
Laterolog 7	a=	l=		a=	l=
Rig Time	2 1/2 HRS				
Job No.	2510-1-1388				
Recorded By	[Signature]				
Address	[Address]				