

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21065-00-00
Spot: NWSE Sec/Twnshp/Rge: 13-33S-29W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: CALHOUN Well Number: 1-13
County: MEADE Total Vertical Depth: 6240 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 9400 N. BROADWAY #400
OKLAHOMA CITY, OK 73114

Conductor Pipe: Size 20 feet: 54 \$202.80
Surface Casing: Size 8.625 feet: 1613 WITH 925 SX CMT
Production: Size 4.5 feet: 3155 WITH 350 SX CMT
Liner: Size _____ feet: _____

Well Type: DH UTC Docket No: _____ Date/Time to Plug: 04/16/2002 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 5600' & 2 SX CMT. 1ST PLUG AT 1645' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/16/2002 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3154'. PERFS AT 3009-3013'. TOC @ 2010'. 04/15/02: PUMP 200# HULLS & 20 SX CMT. DISPLACE WITH MUD. PRESSURED TO 500#. SDON. 04/16/02: 1ST PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 1650', LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 550'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE AND PUMP 10 SX CMT TO SURFACE.

RECEIVED
MAY 01 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1910' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland DIRT #
(TECHNICIAN)

APR 23 2002

Form 02-22

15-119-21065-00-00
5-01-02
2002061729

MP