

1 20219

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,552 - 0000

SW SW NE, SEC. 21, T 33 S, R 28 W ~~XX~~

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8758

Lease Name Nash Well # 1-21

Operator: RAW Energy Corporation of Kansas
Name & Address P.O. Box 1569

County Meade 204.78

Weatherford, TX 76086

Well Total Depth 6301 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1483

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3:30 p.m. Day: 2 Month: 3 Year: 19 89

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5960' PBD 5890' Perfs at 5727-54'

1st plug pump 2 sx hulls ahead of 20 sx cement to perfs, **RECEIVED**
STATE CORPORATION COMMISSION

2nd plug pump 50 sx cement at 1500',

3rd plug pump 30' sx cement at 700', **MAR 07 1989**

4th plug pump 10 sx cement at 40-0'

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: _____ Day: 6 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs, displaced mud,

2nd plug pumped 50 sx cement at 1490',

3rd plug mud to 700', ran 30 sx cement,

4th plug mud to 40', ran 10 sx cement to surface.

Remarks: Used common cement by Sargent's. Recovered 3665' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed Glenn R. Barlow
(TECHNICIAN)

DATE _____

INV. NO. _____
3-6