

1 113016

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,386-0000

SW NW, SEC. 27, T 33 S, R 28 W EX
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5575

Lease Name Heinson Well # 1-27
County Meade 195.98

Operator: Mesa Petroleum Co.
Name & Address: P. O. Box 2009
Amarillo, TX 79189

Well Total Depth 6030 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1513

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 8:00 am Day: 24 Month: December Year: 19 85

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6001' PBTD 5941' Perfs at 5887-5928' Spot cement through 4 1/2" with mud between plugs

1st plug set CIBP at 5830' with 2 sx cement

2nd plug at 1563' with 50 sx cement

3rd plug at 600' with 25 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 pm Day: 24 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5830' with 2 sx cement, 2nd plug at 1563' with 50 sx cement, 3rd plug at 600' with 25 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 3046' 4 1/2" casing. Used common cement by Sargent's
(if additional description is necessary, use BACK of this form.)

INVOICED

(I did not) observe this plugging.

DATE 1-2-86

INV. NO. 113016

Signed James R. Lacey
(TECHNICIAN)

JAN 2 1986
1-2-86