

To: STATE CORPORATION COMMISSION
Wichka State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

7-9

API NUMBER 15-119-20,586-0000
SW SW NW, SEC. 29, T 33 S, R 28 W/EX
2970 feet from S section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4570

Lease Name Mohler Unit Well # 8

Operator: Samedan Oil Corporation

County Meade 19237

Name & Address 9400 N. Broadway, Ste. 700

Well Total Depth 5919 feet

Oklahoma City, OK 73114

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1510

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9 a.m. Day: 9 Month: 7 Year: 19 97

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

logs: 5 1/2" at 5918' w/300 sx cement, PBTD 5885', Perfs at 5608-18'

1st plug set CIBP at 5550' and dump 3 sx cement on top,

2nd plug at 1510' with 80 sx cement,

3rd plug at 650' with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Scott Alberg
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 9 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5558'

2nd plug at 1620' with 80 sx cement, displaced with gel,

3rd plug at 650' with 40 sx cement, displaced with gel,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 4255' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

48600

Signed Gary Winter
(TECHNICIAN)