

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

7-3 15-119-20556-0001
API NUMBER 15- Docket #E-26,993

NW NW SW, SEC. 29, T 33 S, R 28 WXX
2310 feet from S section line
330 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4570
Operator: Samedan Oil Corporation
Name & Address: 9400 N. Broadway, Ste. 700
Oklahoma City, OK 73114

Lease Name Mohler Unit Well # 12
County Meade 188.24
Well Total Depth 5792 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1527

Abandoned Oil Well _____ Gas Well _____ Input Well X SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 3 Month: 7 Year: 1997

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pullers (phone) 316-624-7455

Work: 4 1/2" at 5791' with 200 sx cement, Perfs at 5591-5618'
1st plug set CIBP at 5540' and dump 20' of cement on top,
2nd plug pump 80 sx cement from 1577-1377', 3rd plug pump 40 sx cement at 650-550',
4th plug pump 10 sx cement from 34-4'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 1:30 p.m. Day: 3 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5530' and dump 2 sx cement on top,
2nd plug pumped 80 sx cement at 1598-1334',
3rd plug pumped 40 sx cement at 650',
4th plug pumped 10 sx cement at 40-0'.
Had circulation throughout cement job.

Remarks: Used common cement by Sargent's. Recovered 2510' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed [Signature] (TECHNICIAN)

48560

7-797
RECEIVED
MAY 21 1997
D. H. S. S.