

To: 1 90327  
STATE CORPORATION COMMISSION  
Wichita, State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

7-1  
API NUMBER 15- Docket #E-26,993 15-119-20602-  
NE NE NE, SEC. 31, T 33 S, R 28 w/ 00-01

TECHNICIAN'S PLUGGING REPORT

Operator License / 4570  
Operator: Samedan Oil Corporation  
Name: 9400 N. Broadway, Ste. 700  
Address: Oklahoma City, OK 73114

4950 feet from S section line  
330 feet from E section line  
Lease Name Mohler Unit Well / 16  
County Meade 191.75  
Well Total Depth 5900 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1483

Abandoned Oil Well Gas Well Input Well X SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pullers License Number 6547  
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:45 a.m. Day: 1 Month: 7 Year: 19 97

Plugging proposal received from Kirby Lillard  
(company name) Sargents Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5875' w/250 sx cement, PBD 5818', Perfs at 5608-50'

1st plug set CIBP at 5500' with 20' cement on top, 2nd plug pump 80 sx cement from 1533-1333'  
3rd plug pump 40 sx cement from 650-550', 4th plug pump 10 sx cement from 34-4'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:10 p.m. Day: 1 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5550' with 2 sx cement on top,  
2nd plug loaded hole with mud and spotted 80 sx cement through casing at 1525',  
3rd plug pulled to 650' and pumped 40.sx cement,  
4th plug pumped 10 sx cement at 40'. Stayed full.

Remarks: Used common cement by Sargents Casing Pullers. Recovered 2525' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

Signed [Signature] (TECHNICIAN)

RECEIVED  
KANSAS CORP COM  
MAY 13 1997  
7-2-97  
4 8559