

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,611-0000
SW NW, SEC. 32, T 33 S, R 28 W/E

TECHNICIAN'S PLUGGING REPORT

NOV 14 1988

Operator License # 8475
Operator: Whitaker Enterprises
Name & Address 701 North Kansas
Liberal, KS 67901

3630 feet from S section line
4950 feet from E section line
Lease Name Johannsen Well # 1-32
County Meade
Well Total Depth 5897 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1515

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9 a.m. Day: 2 Month: 11 Year: 19 88

Plugging proposal received from Darrell Christy

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5897' PBD 5845' Perfs at 5620-26'

1st plug set CIBP at 5520' and dump 2 sx cement on top,

2nd plug pump 50 sx cement at 1530',

3rd plug pump 40 sx cement at 740',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 2 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5525' with 2 sx cement on top, load hole with heavy mud,

2nd plug pumped 50 sx cement at 1535-1410', pulled to 740',

3rd plug ran 40 sx cement at 740-640',

4th plug ran 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2650' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(old / ~~AKC XEROX~~) observe this plugging.

DATE 11-21-88

INV. NO. 23057

Signed [Signature]
(TECHNICIAN)