

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21109-00-00  
Spot: SWSE Sec/Twnshp/Rge: 35-33S-28W  
554 feet from S Section Line, 2086 feet from E Section Line  
Lease/Unit Name: ISAAC TRUST B UNIT Well Number: 1-35  
County: MEADE Total Vertical Depth: 3450 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 453 S. WEBB RD. STE 310 PO BOX 7802  
WICHITA, KS 67278

Surface Casing Size: 8.625 feet: 948

Well Type: DH UIC Docket No: Date/Time to Plug: 09/02/2003 1:00 PM

Plug Co. License No.: 8438 Plug Co. Name: POST & MASTIN WELL SERVICE, INC.

Proposal Rcvd. from: CALVIN MIKKELSON Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: 1ST PLUG AT 3130' WITH 100 SX CMT. 2ND PLUG AT 968' WITH 50 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/02/2003 5:10 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SURFACE PIPE PARTED AT 649'. FELL 20' TO 968'. 8 5/8" VOID FROM 649-669'. 1ST PLUG RAN CASING TO 3126' & SPOT 100 SX CMT. 2ND PLUG PULL TO 968' & SPOT 50 SX CMT. 3RD PLUG PULL TO 703' & SPOT 50 SX CMT WITH 3% CC. 4TH PLUG PULL TO 40' & SPOT 10 SX CMT.


RECEIVED  
SEP 08 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
SEP - 4 2003  
KCC Dodge City

Signed   
(TECHNICIAN)

INDEXED  
RAW  
KCC