

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 557 EXPIRATION DATE

OPERATOR Mesa Petroleum Co. API NO. 15-025, 20614-0000

ADDRESS P.O. Box 2009 COUNTY Clark

Amarillo, Texas 79189 FIELD Lexington

\*\* CONTACT PERSON R. E. Mathis PROD. FORMATION Morrow

PHONE (806) 378-4886

PURCHASER Koch Oil Company LEASE Seacat

ADDRESS P.O. Box 1558 WELL NO. 11-19

Breckenridge, Texas 76024 WELL LOCATION

DRILLING TMBR Drilling, Inc. 1300 Ft. from North Line and

CONTRACTOR CONTRACTOR ADDRESS P.O. Box 2608 1100 Ft. from East Line of

Midland, Texas 79702 the N/E(Qtr.) SEC 19 TWP 31S RGE 21W.

PLUGGING CONTRACTOR ADDRESS

WELL PLAT

(Office Use Only)

Grid for well plat with a central well symbol.

KCC [checked] KGS [checked] SWD/REP PLG.

TOTAL DEPTH 5420' PBTD

SPUD DATE 10-27-82 DATE COMPLETED 12-9-82

ELEV: GR 2177' DF 2189' KB 2191'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 660' DV Tool Used? No


THIS AFFIDAVIT APPLIES TO: (Circle ONE) - (Oil) Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Richard Erle Mathis, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.



Richard Erle Mathis (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 22nd day of December

MY COMMISSION EXPIRES: September 3, 1984

RECEIVED

STATE CORPORATION COMMISSION

\*\* The person who can be reached by phone regarding any questions concerning this information.

DEC 27 1982

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR SeacatLEASE 11-19SEC. 19 TWP. 31S RGE. 21WFILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
DST #1 4113-4280  30-60-60-120 REL 180' WCM 1230' SW 1 HP 1986 RHP 1986 IFP 300-416 FFP 433-716 ISIP 1476 FSIP 1476				Wabaunsee	3568
				Elgin	4185
				Heebner	4314
				Brown LM	4493
				Lansing	4516
				BKC	4967
				Cherokee	5122
				B Inola	5226
				Morrow	5244
				Mississippian	5340
DST #2 5219-5255  30-60-60-120 REL 180' DM IHP 2601 FHP 2534 IDP 200-200 FFP 200-200 ISIP 200 FSIP 200					

Report of all strings set—surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	660'	LT/H	250/200	2% CaCl
Production	7 7/8"	5 1/2"	15.5#	5419'	Pozmix/H	125/200	

**LINER RECORD****PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at	Shots per ft.	Size & type	Depth interval
2 3/8"	5229'	None	5246'-5257'	4 JSPF	.50" entry

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Acidized with 750 gal 7 1/2% MCA	5246'-5257'

Date of first production 12-9-82	Producing method (flowing, pumping, gas lift, etc.) Flowing	Gravity 39.8
RATE OF PRODUCTION PER 24 HOURS	Oil 89 bbls.	Gas 16 MCF
	Water 37 %	Gas-oil ratio 180 CFPB
Disposition of gas (vented, used on lease or sold) Vented		Perforations 5246'---5257'