

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5575 EXPIRATION DATE July 1983

OPERATOR Mesa Petroleum Co. APT NO. 15-025-20,644-0000

ADDRESS P.O. Box 2009 COUNTY Clark

Amarillo, Texas 79189 FIELD Lexington

** CONTACT PERSON Randy Z. Nordsven PROD. FORMATION Morrow

PHONE (806) 378-4887

PURCHASER Koch Oil Company LEASE Seacat

ADDRESS Box 2256 WELL NO. 13-19

Wichita, Kansas 67201 WELL LOCATION

DRILLING TMBR Drilling, Inc. #6714 1880 Ft. from North Line and

CONTRACTOR ADDRESS P.O. Drawer 10970 1650 Ft. from East Line of

Midland, Texas 79702-7970 the NE (Qtr.) SEC 19 TWP 31S RGE 21W.

PLUGGING N/A

CONTRACTOR ADDRESS

TOTAL DEPTH 5350' PBTD 5337'

SPUD DATE 3-13-83 DATE COMPLETED 4-18-83

ELEV: GR 2147' DF 2159' KB 2161'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 650' DV Tool Used? yes

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Randy Z. Nordsven, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

SUBSCRIBED AND SWORN TO BEFORE ME this 16th day of May, 1983

MY COMMISSION EXPIRES: 1-26-87

Signature of Randy Z. Nordsven and Notary Public Chris Heubrunner

** The person who can be reached by phone regarding any questions concerning this information.

XC: KCC (O+2), CEN RCDS, ACCTG, OPS(FILE), MAT CONT, GAS CONT, ENVIRONMENTAL CONT, D&M, MC&P, PARTNERS, PROD

MAY 18 1983

CONSERVATION DIVISION Wichita, Kansas

SIDE TWO

OPERATOR

Mesa Petroleum Co. LEASE Seacat

ACO-1 WELL HISTORY

SEC. 19 TWP. 31S RGE. 21W

FILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
			NAME	DEPTH
	4285	4454	Base Heebner	2124' Subsea
	4454	4978	Lansing	2293' Subsea
	4978	5054	Marmaton	2817' Subsea
	5054	5180	Cherokee	2893' Subsea
	5180	5191	Base Inola	3019' Subsea
	5191	5244	Morrow Sand	3030' Subsea
	5244	5350	Mississippian	3083' Subsea

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12"	8 5/8"	24	650	H BJ Lite	150 250	CaCl ₂ 3% CaCl ₂ 2%
Production	7 7/8"	5 1/2"	15.5#	5337'	H LaDensell/H	575 700/475	5% KCL&6#/sx Gilson- 1/4#/sx celloflakes/ite 5% KCL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 JSPF	.50" EHD	5203'-5211'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	5253'	5097'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
900 gals 7 1/2% HCL	5203'-5211'

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
WOPLC	Flowing	-

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	N/A	1300 bbls.	% N/A	N/A

Disposition of gas (vented, used on lease or sold) **vented** Perforations 5203' - 5211'