

ORIGINAL
SIDE TWO
ORIGINAL

Operator Name APX Corporation Lease Name Hinshaw "A" Well # 1H

Sec 32 Twp 33S Rge 39 East West County Morton

RECOMPLETED FORMATION DESCRIPTION:

_____ Log _____ Sample

Name Top Bottom

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth		Type of Cement	# Sacks Used	Type & Percent Additives
	Top	Bottom			
Perforate	_____	_____	_____	_____	_____
Protect Casing	_____	_____	_____	_____	_____
Plug Back TD	_____	_____	_____	_____	_____
Plug Off Zone	_____	_____	_____	_____	_____

Shots Per Foot	PERFORATION RECORD	Acid, Fracture, Shot, Cement Squeeze Record
	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)
2	2691-2717, 2604-2647, 2550-2595, 2519-2531	Brk dwn w/12,000 gal 2% KCL wtr. Frac w/62,000 gal gelled 2% KCL wtr & 157,000# 12/20 sd.

PBTD 2742 Plug Type _____

TUBING RECORD:

Size _____ Set At _____ Packer At _____ Was Liner Run? Y X N

Date of Resumed Production, Disposal or Injection _____

Estimated Production Per 24 Hours _____ bbl/oil _____ bbl/water
1700 MCF gas _____ gas-oil ratio
 @ 110 psig

GABBERT-JONES
DRILLERS WELL LOG

HINSHAW "A" 1H
SEC. 32-33S-39W
STEVENS COUNTY, KS

Commenced: 8-10-88
Completed: 8-13-88
Operator: ANADARKO PETROLEUM CORP.


RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1989
CONSERVATION DIVISION
Wichita, Kansas

Depth		Formation	Remarks
From	To		
0	575	Sand-Clay	Ran 13 jts of 24# 8 5/8" csg LD @ 570' w/150 sks 25/75 Posmix - 2% CC - 1/4# Celoflake 150 sks Common - 3% CC 1/4# Celoflake PD @ 8:15 PM 8-10-88
575	1225	Redbed-Shale	
1225	1278	Shale	
1278	1390	Glorietta Sand	
1390	2915	Shale	
	2915 - TD		Ran 67 jts of 14# 5 1/2" csg LD @ 2910' w/215 sks Class - 20% Diacell D - 2% CC 1/4# Celoflake - 40 sks class C 10% Diacell D - 2% CC 1/4# Celoflake PD @ 1:45 AM 8-13-88

State of Kansas
County of Sedgwick

) I, the undersigned, being duly sworn on oath, state
) that the above Drillers' Well Log is true and correct
) to the best of my knowledge and belief and according
to the records of this office.

GABBERT-JONES, INC.


James S. Sutton, II -- President

Subscribed & sworn to before me this
16th day of August 1988


Lola Lenore Costa

My Commission expires Nov. 21, 1988