

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # _____ EXPIRATION DATE _____

OPERATOR Anadarko Production Company API NO. 15-129-20,636-00-00

ADDRESS Box 351 COUNTY Morton

Liberal, Kansas 67901 FIELD Dunkle

** CONTACT PERSON Paul Gatlin PROD. FORMATION Wabaunsee

PHONE (316) 624-6253

PURCHASER Panhandle Eastern Pipe Line Company LEASE Eagley "D"

ADDRESS Box 828 WELL NO. 1

Liberal, Kansas 67901 WELL LOCATION C NW NE

DRILLING CONTRACTOR Gabbert-Jones, Inc. 660 Ft. from North Line and

ADDRESS 830 Sutton Place 1980 Ft. from East Line of

Wichita, Kansas 67202 the NE (Qtr.) SEC 2 TWP 33S RGE 41W.

PLUGGING CONTRACTOR _____ WELL PLAT _____ (Office Use Only)

ADDRESS _____

TOTAL DEPTH 3100 PBDT 3064

SPUD DATE 6/20/82 DATE COMPLETED 7/14/82

ELEV: GR 3423 DF 3427 KB 3428

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 637 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, (Gas), Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T


Paul Campbell, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Paul Campbell
(Name)
Division Operations Manager

SUBSCRIBED AND SWORN TO BEFORE ME this 16th day of July, 19 82.

19 82 .

MY COMMISSION EXPIRES: 

Elizabeth J. Hooper
(NOTARY PUBLIC)

** The person who can be reached by phone regarding any questions concerning this information.

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Anadarko Production Co. LEASE Eagley "D" No. 1 SEC. 2 TWP. 33S RGE. 41W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0'	335'		
Sand-Redbed	335'	645'		
Redbed-Sand	645'	1013'		
Sand-Shale	1013'	1753'		
Sand	1753'	2069'		
Shale	2069'	2420'		
Shale-Lime	2420'	2621'		
Lime-Shale	2621'	2825'		
Shale-Lime	2825'	3049'		
Lime-Shale	3049'	3100'		
TD	3100'			

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	20#	637	Common	550	3% CaCl
Production	7-7/8	4-1/2	10.5#	3096	Litewate SS Pozmix	500 150	.05% CFR2 .05% CFR2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			2	.46	2896-2902'

Size	Setting depth	Packer set at
2-3/8	2879'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 Gal 7-1/2% HCl	2896-2902

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
SI for Pipeline	Flowing	
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF 686
	Water %	Gas-oil ratio bbls. CFPB
Disposition of gas (vented, used on lease or sold) To be sold		Perforations 2896-2902 Wabaunsee