

ORIGINAL

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

API NO. 15- 191 - 22198-00-00

Operator: License # 30269
Name: Argent Energy, Inc.
Address 110 S. Main, #510
City/State/Zip Wichita, KS 67202

County Sumner
SE SW NE Sec. 14 Twp. 30S Rge. 1 X E/W
2310 Feet from SW (circle one) Line of Section
1650 Feet from EW (circle one) Line of Section

Purchaser:
Operator Contact Person: James Remsberg
Phone (316) 262-5111

Footages Calculated from Nearest Outside Section Corner:
NE, SE, NW or SW (circle one)
Lease Name McKowen Well # 1
Field Name Unnamed

Contractor: Name: VAL Energy, Inc.
License: 5822

Producing Formation None
Elevation: Ground 1232' KB 1237'
Total Depth 3919 PBDT

Wellsite Geologist: Rick Harris

Designate Type of Completion
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

Amount of Surface Pipe Set and Cemented at 262 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cnt.

If Workover/Re-Entry: old well info as follows:

Drilling Fluid Management Plan AITP OVA
(Data must be collected from the Reserve Pit)

Operator: _____
Well Name: _____
Comp. Date _____ Old Total Depth _____
Deepening _____ Re-perf. _____ Conv. to Inj/SWD
Plug Back _____ PBDT
Commingle Docket No. _____
Dual Completion Docket No. _____
Other (SWD or Inj?) Docket No. _____
4-24-92 5-1-92 5-1-92
Spud Date Date Reached TD Completion Date

Chloride content 5,000 ppm Fluid Volume 2250 bbls
Dewatering method used evaporation
Location of fluid disposal if hauled offsite:
Operator Name _____
Lease Name _____ License No. _____
Quarter Sec. Twp. S Rng. E/W
County _____ Docket No. _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature James C. Remsberg
Title President James C. Remsberg Date June 9, 1992
Subscribed and sworn to before me this 9th day of June, 1992.
Notary Public Julie O. Koker
Date Commission Expires Dec. 4, 1993
My Appl. Exp. 12-4-93

K.C.C. OFFICE USE ONLY
F Letter of Confidentiality Attached
C Wireline Logs Received
C Geologist Report Received
Distribution JUN 11 1992
 KCC SWD/Resp
 KGS Plug/Sealant
Wichita, Kansas
(Specify)

Operator Name Argent Energy Lease Name McKowen Well # 1

Sec. 14 Twp. 30S Rge. 1 East West
County Sumner

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
(Attach Additional Sheets.)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
(Submit Copy.)

List All E.Logs Run:

Gamma Ray, Guard, Caliper

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
Kansas City	2833'	(-1596')
Cherokee Shale	3316'	(-2079')
Mississippian	3430'	(-2193')
Kinderhook	3824'	(-2587')
Simpson	3876'	(-2639')
RTD	3919'	(-2682')

CASING RECORD

New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Conductor	17-1/2	13-3/8	46	65'	40-60 poz	90	2% gel/3% CC
Surface	12-1/4	8-5/8	23'	262'	40-60 poz	160	2% gel/3% CC

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD Size Set At Packer At Liner Run Yes No

Date of First, Resumed Production, SWD or Inj. Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil Bbl's. Gas Mcf Water Bbl's. Gas-Oil Ratio Gravity

Disposition of Gas: Vented Sold Used on Lease (If vented, submit ACO-18.) METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Production Interval

ORIGINAL ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

New

Date	4-24-92	Sec.	14	Twp.	30	Range	1	Called Out	2 ⁰⁰ PM	On Location	6 ⁰⁰ PM	Job Start	8 ⁰⁰ PM	Finish	8 ³⁰ PM
Lease	Ms Kowan	Well No.	#1	Location				Pack 25 1/2 w/s w/s		County	Summa	State	KS		
Contractor	Val. Drilling R/g #1				Owner				SAME.						
Type Job	Drill P.O. Job Conductor				To Allied Cementing Co., Inc.				You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.						
Hole Size	17 1/2		T.D.		68 ft		Charge To				Argent Energy Inc				
Csg.	13 3/8		Depth		64 ft		Street				110 S. Main Suite 510				
Tbg. Size			Depth				City				Wichita State KS 67202				
Drill Pipe			Depth				The above was done to satisfaction and supervision of owner agent or contractor.								
Tool			Depth				Purchase Order No.								
Cement Left in Csg.	15 ft		Shoe Joint				X <i>Dal Smock</i>				Thank you				
Press Max.			Minimum				CEMENT								
Meas Line	49 ft		Displace		7.6 bbl		Amount Ordered				90 ⁶⁰ 243				
Perf.							Consisting of								

EQUIPMENT		
<i>Mixed Band</i>		
Pumptrk	No. 120	Cementor <i>Mike</i> Helper <i>Quane</i>
Pumptrk	No.	Cementor Helper
Bulktrk	208	Driver <i>HUNT</i>
Bulktrk		Driver

DEPTH of Job <i>64 ft</i>		
Reference:	<i>Pump Truck Charge</i>	<i>380.00</i>
<i>80</i>	<i>Milage charge</i>	<i>160.00</i>
<i>1</i>	<i>13 3/8 wooden plug</i>	<i>79.00</i>
Total		<i>\$ 619.00</i>

Remarks: *Cement did circulate*

Handling	<i>90</i>	<i>1.00</i>	<i>90.00</i>
Milage	<i>80</i>		<i>288.00</i>
Total			<i>805.50</i>

Floating Equipment RECEIVED
 CORPORATION COMMISSION
 TOTAL \$ *1424.50*
 JUN 1 1992 \$ *284.90*
 CONSERVATION DIVISION
 Wichita, Kansas \$ *1139.60*

Allied Cementing Co. Inc
Mike Mersch
Thank you
4/29

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

ORIGINAL

Phone Plainville 913-434-2812
 Phone Ness City 913-798-3843

ALLIED CEMENTING CO., INC.

No 2849

New Home Office P. O. Box 31

Russell, Kansas 67665

Date	4-25-92	Sec.	14	Twp.	30	Range	1	Called Out	4 ³⁰ AM	On Location	8 ³⁰ AM	Job Start	9 ³⁰ AM	Finish	10 ³⁰ AM
Lease	McKowan	Well No.	#1	Location				Peck 25 1w 25 w/s	County	Sumner	State	KS			
Contractor	Uel Drilling Rig #1														
Type Job	Surface pipe job														
Hole Size	12 1/4	T.D.	265 #												
Csg.	4 5/8	Depth	262 #												
Tbg. Size	Depth														
Drill Pipe	Depth														
Tool	Depth														
Cement Left in Csg.	15 #	Shoe Joint													
Press Max.	Minimum														
Meas Line	✓ 245 #	Displace	15.4 bbl												
Perf.															

Owner SAME
 To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To Argent Energy Inc
 Street 110 S. Main Suite #510
 City Wichita State Ko. 67202
 The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No.
 X *Dal Smith* Thank
 CEMENT 704
 872

Amount Ordered 160 2/40 2+3
 Consisting of
 Common 96 5.25 504.00
 Poz. Mix 64 2.25 144.00
 Gel. 3 6.25 NIC
 Chloride 5 21.00 105.00
 Quickset

Handling	160	1.00	160.00
Mileage	80		512.00
		Sales Tax	
		Sub-Total	
		Total	1425.00

EQUIPMENT

Acad Band

Pumptrk	No. 120	Cementer	<i>Mike Duane</i>
Pumptrk	No.	Cementer	
		Helper	
Bulktrk	209	Driver	<i>YANCY</i>
Bulktrk		Driver	

DEPTH of Job 262 #

Reference:	Pump Truck Charge	380.00
	Mileage charge	NIC
	1 5/8 wooden Plug	42.00
	Sub-Total	
	Total	422.00

Remarks: Cement did not circulate

Floating Equipment
 RECEIVED
 STATE CORPORATION COMMISSION
 JUN 10 1992 - 1847.00
 - 369.40
 CONSERVATION DIVISION
 Wichita, Kansas
 \$ 1477.60

Allied Cementing Co. Inc
 Mike Munsch

Thank you
 GCO

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

ORIGINAL

MAY 07 1992
 Phone Plainville 913-434-2812
 Phone Ness City 913-798-3843

ALLIED CEMENTING CO., INC. No. 3044

Home Office P. O. Box 31

Russell, Kansas 67665

New

Date	5-1-92	Sec.	14	Twp.	30	Range	1	Called Out	12:00PM	On Location	4:00PM	Job Start	5:00PM	Finish	1:00PM	
Lease	McKowen	Well No.	#1	Location				Peck, 25, 1W, Kas, W/S	County	Summer	State	KS				
Contractor	Val Energy															
Type Job	Rotary Plug															
Hole Size	7 7/8"		T.D. 3919'													
Csg.	Depth															
Tbg. Size	Depth															
Drill Pipe	4 1/2"		Depth 1900'													
Tool	Depth															
Cement Left in Csg.	Shoe Joint															
Press Max.	Minimum															
Meas Line	Displace															
Perf.																

Owner Same
 To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To Argent Energy, Inc.
 Street 110 S Main Suite 510
 City Wichita State Ks. 67202
 The above was done to satisfaction and supervision of owner agent or contractor

Purchase Order No.
 X Dale Smith

CEMENT

Amount Ordered	130 SKS 60/40 620 Gel,		
Consisting of			
Common	78	5.25	409.50
Poz. Mix	52	2.25	117.00
Gel.	8	6.75	54.00
Chloride			
Quickset			

EQUIPMENT

#	No.	Cementer	Tim
Pumptrk	181	Helper	Cary
#	No.	Cementer	Mark
Pumptrk	168	Driver	
Bulktrk		Driver	

Handling	130	1.00	130.00
Mileage	80		416.00
Sub Total			
Total	1126.50		

DEPTH of Job

Reference:	1900'	
80	Pumptrk Charge	380.00
1	Pumptrk Mileage	160.00
	8 3/4 Dryhole Plug	21.00
	Sub Total	
	Tax	
	Total	561.00

Remarks: Mixed - 35 SKS at 1900'
 50 SKS at 310'
 25 SKS at 60' 1/2 Bridge
 10 SKS in Rathole
 10 SKS in Waterwell

STATE RECEIVED
 CORPORATION COMMISSION
 1687.50
 Disc - 337.50

JUN 1 1992
 CONSERVATION DIVISION
 Wichita, Kansas \$1350.00
 Thanks Allied Cementing
 By Tim Dickson