

SIDE TWO

Operator Name JMA Resources, Inc. Lease Name Roy Green Well # 3-19

Sec 19 Twp 34S Rge 34 XX East West County Seward

RECOMPLETED FORMATION DESCRIPTION:

X Log Sample

<u>Name</u>	<u>Top</u>	<u>Bottom</u>
Upper Chester Limestone	6208'	6256'

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth		Type of Cement	# Sacks Used	Type & Percent Additives
	Top	Bottom			
<u>Perforate</u>					
<u>Protect Casing</u>	-- None --				
<u>Plug Back TD</u>					
<u>Plug Off Zone</u>					

Shots Per Foot	PERFORATION RECORD	Acid, Fracture, Shot, Cement Squeeze Record
	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)
2 SPF	6215-6228' (13')	Acidized: 1500 Gallons 15%+40 Ball Sealers via 2-7/8"
		Frac'd: 7500 Gallons Gelled 2% KCL - Pad
		7500 Gallons 20% Acid
		1100 Gallons 2% KCL - Flush
		Above via 2-7/8"

PBTD 6300' Plug Type CIBP @ 6300' + 1 sx cement on top

TUBING RECORD:

Size 2-7/8" Set At 6189' Packer At 6190' Was Liner Run? Y X N

Date of Resumed Production, Disposal or Injection 5-20-89

Estimated Production Per 24 Hours 1 bbl/oil 8.34 bbl/water

503 MCF gas 503,000-1 gas-oil ratio