

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Unruh of Imperial Oil Co. has this
date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company

Complete Address: Box 784, Great Bend, Kansas

Lease Name: Patton Well No. 3

Location: C NW SW Sec. 6 Twp. 33 Rge. 29 XX (E) (W)

County: Meade Total Depth 5946' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

8 5/8" to 1535' circulated w/ cement. 5 1/2" to 5928' cemented.


Top perforations 5812' Plug bottom w/ 50 sacks cement.

Top of cement 5515' Mud 5515' to 600'

Spot 4 1/2 Yds. ready Mix 600' to 300' Mud 300' to 30'

Plug & 1/2 Yd. ready mix 30' to 0'.

Very truly yours,


Conservation Division Agent