

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of William Gruenerwald has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: William Gruenerwald & Assoc., Inc.

Complete Address: Box 909, Colo. Springs, Colo.

Lease Name: Sleeper Well No. 1

Location: C NW SE Sec 25 Twp. 33 Rge. 31 (X) (W)

County Seward Total Depth 6135' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1584' circulated w/ cement. 4 1/2" to 6134' cemented.

Top perforations 6102' Plug bottom w/ 15 sacks cement.

Top of cement 6000' Mud 6000' to 700'

Rock bridge & 40 sacks cement 700' to 575' Mud 575' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Eves
Conservation Division Agent