

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION FEB 26 1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Meyer of Abercrombie has this

date requested permission to plug the following described well:

Mr. Meyer guarantees payment of the plugging fee.

Operator's full Name: A.L. Abercrombie Inc.

Complete Address: 801 Union Center Bldg., Wichita, Kansas

Lease Name: Fredrick Well No. 6

Location: SE SW Sec. 26 Twp. 33 Rge. 31 (E) (W)

County: Seward Total Depth 5925' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Meyer was instructed to plug the well as follows:

8 5/8" to 1242' circled w/ cement. 5 1/2" to 5924' cemented.

Top perforations 5836' Plug bottom w/ 20 sacks cement

Top of cement 5550' Mud 5550' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Lewis Conservation Division Agent